

**ADDENDUM NO. 2**

TO

**PROJECT DOCUMENTS**

FOR

**Manila Senior Center**

Manila, AR

ACEDP GRANT #790-08840-14

**April 17, 2017**

**This addendum forms a part of the Contract Documents and modifies or interprets the Project Manual and Drawings, as noted below. Acknowledge receipt of this Addendum on the Bid Form. Failure to do so will subject bidder to disqualification.**

**BID DATE REMAINS AS FOLLOWS:**

Tuesday; April 18, 2017 at 2:00pm Manila City Hall

**A. INSTRUCTIONS TO BIDDERS: N/A**

**B. BID FORM: N/A**

**C. PROJECT DRAWINGS:**

**1. Drawing A 1.1 FLOOR PLAN:**

DOOR SCHEDULE- **CLARIFICATION-** Door 102 is a PAIR of 3'-0" x 7'-0" doors

**2. Drawing P 1.1 PLUMBING DRAIN PLAN:**

**a. CLARIFICATION-** There are no roof drains on this project.

**b. RPZ DRAINS -** Add a 3" Floor drain FD-1 under RPZ-2. RPZ-1 shall drain to JS-1.

**3. Drawing P 1.2 PLUMBING SUPPLY PLAN:**

**a. PLUMBING EQUIPMENT SCHEDULE –** RPZ-2 shall be 1" size. Add CP-1 circulating pump, Amtrol RBW2, 120v, 1/12 HP.

**b. PIPING MATERIALS CLARIFICATIONS –** Sanitary drain piping shall be PVC as scheduled. The 3 compartment sink drain to the floor sink shall be copper per the detail. Water supply piping shall be insulated per the Plumbing Insulation Schedule.

**c. GAS PIPE SIZES –** The low pressure riser into the building and all pipes serving more than one unit shall be 1-1/4". All individual unit runout pipes shall be 1". The regulator shall be sized per the manufacturer's instructions for 300 MBH.

**d. ZONE ISOLATION VALVES-** Provide isolation valves for the restrooms, kitchen and each hose bibb.

**e.**

4. **Drawing E 1.1 ELECTRICAL PLAN:**

**CLARIFICATION-** Electrical power service and panels shall all be 208V/3PH.

**D. SPECIFICATIONS:**

2. **SECTION 07210 Building Insulation:**

a. **ADD** Icynene ProSeal MD-C-200 v3spray foam as an approved alternate

**END OF ADDENDUM NO. 2**