andrew hicks | architect

209 North Pierce Little Rock Arkansas, 72205 www.andrewhicksarchitect.com

voice 501.219.1614 fax 501.219.1613

Andrew Hicks: Project Manager

Phone: (501) 219-1614 FAX: (501)219-1613

andrew@andrewhicksarchitect.com

Re: A K-4 CLASSROOM ADDITION BUILDING

Owner: SLOAN HENDRIX SCHOOL DISTRICT/ IMBODEN, AR

Superintendent of Schools

Mr. Clifford Rorex

Highway 115 / Greyhound Circle / PO Box 1080,

Imboden, Arkansas 72434

Project to be located on:

Sloan Hendrix School Campus, Imboden, Arkansas 72434

ADDENDUM #2

April 20, 2017

Modifications or clarifications to original plans and specifications:

1. ATTENDEES OF THE PRE-BID CONFERENCE ARE ON THE ATTACHED LIST

SITE WORK ,EARTHWORK AND FOOTINGS

2. Contractors shall refer to addendum #1, items #6 and 7. In addition to these items #6 and #7in addendum # 1 Contractor shall be required to excavate three (3) test excavation strips to determine the presence and depth of possible rock that may exist under the locations of the new footings. The test excavations

A NEW K-4 CLASSROOM ADDITION Sloan Hendrix School Campus Addendum #2 Page 1 of 5 shall be done on the east side of the building where the footings will be the closest to original grade. Each test excavation strip shall be 24" wide x 15' (feet) long x 24" deep, three required at the north end, south end and middle of the north side of the building or as determined by the Architect. The results of the test shall be used to determine if adjusting the Finish Floor elevation of the new building may help in avoiding rock excavation by raising the building elevation or conversely may allow reducing building fill by lowering the building.

- 3. After the bids are taken and the Contract is awarded the Contractor with the low bid for this project shall be prepared to provide to the owner a unit price deduct and a unit price add for adjusting the buildings Finish Floor elevation in increments of 4" up to a maximum of 12" in either direction. Architect is aware that lowering the building may increase ramps lengths and raising the building may allow for a decrease in ramp lengths which will also affect the length of the Linking Corridor to the existing building.
- 4. Section 02200 –Earthwork 4.B/G.1—clarification. All fill shall be placed in 8" layers. (not to exceed)
- 5. Section 02200 –Earthwork 5.A.1—clarification- No need for any area to be cross sectioned.
- 6. Section 02200 –Earthwork 5.A.1—clarification- footings may be placed on a minimum of 24" of properly compacted, approved earth fill.
- 7. Termite Control- disregard any reference to North Carolina Law. All Termite control shall be done in accordance with Arkansas Law.
- 8. All clearing and grubbing shall be done by the Owner before the start of Construction.
- 9. Disregard any reference to an underground drainage system. The building has NO underground drainage system. Concrete Splash blocks are to be provided at all downspouts.
- 10. The existing sanitary sewer from the existing school building is to be replaced in its' entirety from 5' outside the existing school to the existing

manhole. If the flow lines and grades permit, the new sewer to serve both the existing school and the new addition as shown on the plans may be run in the existing sewers trench to avoid new rock excavation as much as possible. If additional rock excavation is required it shall be paid for out of contingency funds.

11. A temporary construction fence 6' high with a truck sized gate shall be required to be installed to secure the construction area from the immediate play area to the south of the construction area. See the attached map for the location and extent on the fence. The contractor shall determine the amount of security and fencing required at the north end of the construction area and shall take the necessary steps to protect students and others who might be using the adjacent school areas.in those areas.

EXTERIOR FINISHES AND METAL BUILDING

- 12. METAL BUILDING- contractor shall disregard any reference to a vented ridge. No vented ridge is required on the metal building
- 13. METAL BUILDING- contractor shall disregard any reference to a vented soffit panels. No vented ridge is required on the metal building. Metal building fabricator shall provide framing for metal soffits as part of the building system and as required to coordinate with light gauge framing.
- 14. ROOF PURLINS- no 8" roof purlins shall be installed.
- 15. ROOF INSULATION. The metal building fabricator shall determine the size and depth of the purlins based on structural requirements- either a 10" or 12". For the purposes of the bid assume that a 12" purlin shall be installed and that the Simple Saver type of insulation (or equal) shall be bid as 9.5" (R30) of Simple Saver type insulation system below 3.5" (R11) of un-faced fiberglass insulation supplied by the metal building company. If the purlin is determined by the metal building fabricator to be less than 12" the contractor shall be prepared to negotiate a savings to the owner for less insulation thickness.
- 16. METAL BUILDING- The roof LIVE LOAD shall be 20 psf (twenty pounds per square foot). Disregard any reference to any other live load.

- 17. METAL BUILDING- No collateral loading is required.
- 18. METAL BUILDING The exterior finish on all wall panels shall be a Kynar finish. Contractor shall disregard any references to SP finish.
- 19. METAL BUILDING The exterior wall panels shall be a PBR type metal panel with a Kynar finish. Color shall be selected by owner from standard colors. Contractor shall disregard any references to any other type wall panel
- 20. The contractor shall disregard any reference to exterior brick masonry in the construction documents. The building has NO brick masonry.
- 21. <u>LIGHT GAUGE METAL FRAMING</u>. In lieu of original specifications all EXTERIOR light gauge metal wall studs are to be 18 gauge. MINIMUM

INTERIOR, FINISHES and DOORS

- 22. <u>LIGHT GAUGE METAL FRAMING</u>. In lieu of original specifications all INTERIOR light gauge metal wall studs are to be 20 gauge. MINIMUM
- 23. INTERIOR WALLS -Gypsum wall board. Standard 5/8" type x gyp bd. shall be installed in all mechanical rooms in lieu of the HIGH IMPACT gyp. bd. that shall be installed in the other areas of the building.
- 24. CEILINGS- All acoustic ceilings panels are to be white color and installed in a black grid. In lieu of the original ceiling tile specified the contractor shall provide and install an Armstrong tile- Fine fissured- 1713. The tile and grid shall be the same size as original specification.
- 25. DOORS- Pioneer brand hollow metal doors and frames shall be considered an equal to CECO or Curries brand for the purposes of the bid. Also, Deansteel safe room doors shall be considered an equal to the StormPro safe room doors.

PLUMBING AND MECHANICAL

26. As per the plumbing drawings and sheet P001 the contractor shall provide a 1-1/2" (one and one-half inch) water meter from the City of Imboden to service a 2-1/2" water line with a minimum of 40 pounds of pressure. Verify pressure in the city water line at the location of the meter.

ELECTRICAL AND LOW VOLTAGE

- 27. FIRE ALARM In lieu of tying onto the existing fire alarm system in the adjacent existing building the contractor shall provide and install a complete stand-alone fire alarm system with a new panel to serve only the new addition. See the seven (qty.) attached fire alarm addendum sheets attached as a part of this addendum.
- 28. Electrical engineer has revised Electrical documents to reflect the ductless split system HVAC system in the original design. See the seven (qty.) electrical addendum sheets attached as a part of this addendum.

Sheet E3.1 pdfs 1 thru 4 – I revised circuitry to Ductless Split System units and changed designations to match Mechancial plans...

Sheet E5.1 – Added Fire Alarm Riser Diagram

Sheet E5.2 pdfs 1 and 2 – Revised panel schedules to reflect HVAC circuitry to Ductless Split Systems

29. INTERCOM SYSTEM. – eliminate the intercom and bell system as a part of this bid. The owner will obtain a separate contractor to install a new intercom and bell system for this building and other building in the complex. Contractor shall be required to coordinate with the separate intercom contractor as they install the new Intercom System in this K-4 addition building.

Sloan Hendrix Schools K-4 Classroom Addition
Sloan Hendrix School District

PRE-BID ATTENDANCE RECORD

Thursday, April 13, 2017

ATTENDEE'S NAME	COMPANY NAME	PHONE NUMBER	TIME IN
E-MAIL ADDRESS	TRADE	FAX	TIME OUT
Denovio Mors	$\widehat{}$	(d) (1, 1, 1)	1000
一つのでなり、一人のうり	一のではない、つれてみたら	(F) (26) (SCA)	10.00

Mark Hanky	Cornerstone Construction	1812-176 (614)	16:20
mountous acebuilders, com	GC	(479) 967-2167	
Richard Singlitic	Corherstone Construction	479-967-2181 10:20	10:20
Richica CCF builders, can		479-967-2167	

TKS Planting Committee	Bright Barksdale BKB Plumbing	Keith Chung Kchung & Laterc con Tate Gen Contr	Ryan Buffrington @ Sucylobal Met Buffrington Esporthers 573-7185-13168 10:30	Clarkgeneral Usbiglobalnet	Corpet Clark Clark Contradas, 870.866-6711
870-243-177	870-243-7241 10:30	935-4428	573-765-હીલ્ટ	870-686-6712	. EN-866-6711
	10:30		10:30		

Sloan Hendrix Schools K-4 Classroom Addition
Sloan Hendrix School District
PRE-BID ATTENDANCE RECORD
Th

Thursday, April 13, 2017

ATTENDEDIC NAME	COMBANY NAME	DHONE NI MARER TIME IN
E-MAIL ADDRESS	TRADE	
Notern Moister	Flect Ca)	870-340-7188 10:50
Jeneister DISARDICON		
Shime Kec	Exvition	870 932-8470 10:50
BRANDON HARLAN	NOACON, INC.	501-723-8364 10:50
bids@ncacen.com	60	866 809-5606
Down Minmuno	Workhorse Physiolog LLC	870-844-0175 lo:52
Workhorsephumbing@igmail.com belook Plumbing	belook Divusbing	
Soe Gibson	RAB Mechanical	972-1560 /0153
Des @ Submechanical. Com		
Kyan Marris	Abans & Cope Flowburg	935-566

Sloan Hendrix Schools K-4 Classroom Addition Sloan Hendrix School District PRE-BID ATTENDANCE RECORD

Thursday, April 13, 2017

ATTENDEE'S NAME	COMPANY NAME	DUONIE NI IMBED	
E-MAIL ADDRESS	TRADE		TIME OUT
Mike Ainold	Precise Salar and Power	870-698-1754	
precise solar and power os yahoo	Electrical / HVAC	870-367-2266	
Bandon Passley	East Ankansas Flectical Colonales	875-275-0840	
Brandon @ FAE Contractors, co.m	Electrical		
Darren Strain	Sweet's Lont.	\$70-198-8922	10:4A
Sweet's Lont.	Site Work		
MUSTACKON			
1007	HUAC	8709782AS	
Ect Muchather	PAI	21287122	10:45
SECTIO POLIMAN PANTAPARONE COM	Proces inc	501 1276500	
RLHConstruction XH Construction		15 th 1634	

Sloan Hendrix Schools K-4 Classroom Addition Sloan Hendrix School District PRE-BID ATTENDANCE RECORD

Thursday, April 13, 2017

ATTENDEE'S NAME	COMPANY NAME	PHONE NUMBER	TIME IN
E-MAIL ADDRESS	TRADE	FAX	TIME OUT
Brad Books +	Processon Plus Constanton Tens.	870-373-082 3	10:57
precisionalis construction Dyalic. com	Come of Contractor	820 00-4855	
hard Borlot	Talica		
Souko A Phong & Valor	Dict Liguent	878-322-7113	10:57
Joh Band	Brand Custon Hading	870-935-934 10:58	10:58
Brand frucking & & bc gobolnet	Earth work		
Damien Closen	Long	617-610-8671	11:00
Doran @CLon Electric LLC. don			
decemy Edgar		870-215-7659	10:55
Secony@ Edges Flectric inc. com	EE;		
JANEINE SIMPSON	Cos Pleasaic	870-70 BX	11:00
CSimpon aginail. Com			
ς			

5 gt 6

Sloan Hendrix Schools K-4 Classroom Addition Sloan Hendrix School District PRE-BID ATTENDANCE RECORD

Thursday, April 13, 2017

TRADE EXAMPLE
GC. ELEC., MECH. HVAC, PLUM, ROOF, ETC.
11:00 AM

ATTENDEE'S NAME E-MAIL ADDRESS	COMPANY NAME TRADE	PHONE NUMBER FAX	TIME IN TIME OUT
Mark for	Control Heating & Could the	870,935,369	
mpone controlly con	ナッチへ	872.5\$5-4031	
BODD Musselly	Murphy Brothers Constitution	870-919-2572	10:55
musphy boll a fresh com	512		
Matt Harnes haynes plumbinging @ att.net	Plumbing	501-362-4607	75:01
HAYNESDEMPING INCEPTING	PLUMIZING-	501-3629407	10:59
Rodrey Juckson Progressive Technologies	Sourity; Low voltage	501-205-6370	10255
a hickman (conturted , Net	Dirt w/c Conding	8708692841	10:55
Keliv Smith	Smith Electric	870-7580283	10:55
Trial & March	CISTING O DINGTO	55:01 858-98-01.5	75:01
LEUDINOUX	Y CUSHIMPU EIOU	820-111-0218	
) 			

Dr. (OT

Sloan Hendrix Schools K-4 Classroom Addition Sloan Hendrix School District PRE-BID ATTENDANCE RECORD
Th

Thursday, April 13, 2017

ATTENDEE'S NAME	COMPANY NAME	PHONE NUMBER	TIME IN
E-MAIL ADDRESS	TRADE	FAX	TIME OUT
Dustin Murolm	DS Murphy Construction	870 930699	
on@yaloo,w	Stol	8702681869	
Hurter Sailey	BAILEY CONTRACTORS	870 933 9612	
hute e bailey cx. com	begeral	870 933 9618	
Aaron Tate lugge Tate	AWT Constructors	870-919-197	
agron. autconstructors & smail.opm	om General	870-520-6380	
Brym Roger	ALAMATEC	6102-428-109	
blogui e a) some c. com	1		
we thouse	Banky corre	1879-058-018	,
lee @ bailey gc. com	GENE (10) CONTIC	870-933-9618	
Gerald Provened	Provency Congt. Co., Dr.	811 - X27-7225	
provioust to attitet	General Contractor	820-283-7542	

MPLE 7ct 8

Sloan Hendrix Schools K-4 Classroom Addition
Sloan Hendrix School District
PRE-BID ATTENDANCE RECORD
Th

Thursday, April 13, 2017

ATTENDEE'S NAME E-MAIL ADDRESS	COMPANY NAME TRADE	PHONE NUMBER FAX	TIME IN
Kwin Coll	Kevin Cock Electric	1959-655-028	11200
┛			
Chaze Ma Pikrson	W.A Stewart Electric Co.	870-952-3626	11:00
emephors & Stewartec.com	Electrical	870-132-3662	
Berry Phillips	Fields Heating 4 A/C	870-523-6310	
Fields Hooring + He	HVAC	523-3521	

Sloan Hendrix Schools K-4 Classroom Addition Sloan Hendrix School District PRE-BID ATTENDANCE RECORD


Thursday, April 13, 2017


TRADE EXAMPLE


GC. ELEC., MECH. HVAC,PLUM, ROOF, ETC. 11:00 AM


ATTENDEE'S NAME E-MAIL ADDRESS	COMPANY NAME TRADE	PHONE NUMBER	TIME IN
lick Rovie grand olymputacion General olypus construction	General olypus construction	570-897-1251 870-932-6670	


SAS












SCALE: NONE



-to main telephone terminal board - 2 dedicated telephone lines - 3/4" c

PANEL "MP" SERVES CC 1 CU-1 (2#10, #126, 3/4°C) 7 9 CU-2 (2#10, #126, 3/4°C) 7 13 CU-4 (2#10, #126, 3/4°C) 11 13 CU-6 (2#10, #126, 3/4°C) 19 25 F-1 27 F-2 29 F-3 31 F-4 33 F-6 33 F-6 35 DSCU-1 41 DSCI 43 DSCU-3 45 DSCU-3 45 DSCU-3 57 SPARE 58 SPARE 59 SPARE 59 SPARE 59 SPARE 59 SPARE
SCHEDULE RUN THRU LTG RELAY PANEL (*)
LOAD 2160 2160 2160 2160 1350 1350 1350 1350 1500 2160 2160 2160 2160 2160 2160 2160 21
VOLTS 1 PHASE 4 BRACED: 22 KAIC BRACED: 22 KAIC CIRCUIT BRACED: 2160 COLORDO BUS AND CIRCUIT CIRCUIT BRACED: 22 KAIC CIRCUIT OUAD (VA) POLES PH A PH B COLORDO
WIRE 60 HZ WIRE 60 HZ MAINS: FEED FROM SERVES PAMEL (*)
MAINS: 400A MLO (2#10, #12G., 3/4°C)

	83	<u>&</u>	79	77	75	7.3	71	69	67	65	63	61	59	57	55	53	51	49	47	4 5	43	(CKT#			
PHASE TOTALS	SPARE	SPARE	SPARE	SPARE	SPARE	73 SPARE	SPARE	SPARE	SPARE	SPARE	SPARE	SPARE	SPARE	SPARE	SPARE	FACP	RECEPTACLES - MISC		SERVES		PANEL "LP"					
	-		-		ı	-	1	_	-	_	-	_	-		-	_	-	_	-	-	-	(*)	LTG RELAY PANEL	RUN THRU	SECT 2 OF 2	
_	-		-		-		-		-		-		-		-		1080	1	1080	1	1080	PH A PH	LOAD (VA)			Σ
-	20/1	- 20/1	20/1	- 20/1	20/1	- 20/1	20/1	- 20/1	20/1	- 20/1	20/1	- 20/1	20/1	- 20/1	20/1	400 20/1	20/1	1080 20/1	20/1	1080 20/1	20/1	B POLES		CIRCU	MOUNTED: SURFACE BRACED: 22 K REMARKS: W/ SEPERATE GROUND BUS	SFRVICE: 240/120
																									JRFACE / SEPI	5/150 150
7	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	20/1	POLES	TRIP/	CIRCU	₹	
-	-		_		V				_		1080		1080		1080		1080		1080		1080	S PH A			BRACED: 22 KAIC TE GROUND BUS	VOLTS 1 PHASE 4 WIRE
<u>}</u>		-		-	*	_		_		-		1080		1080		1080		1080		1080		В НА			BUS KAIC	ASF 4
~	-	-	-	-	3	_	-	_	-	_	-	-	-	_	-	_	_	-	_	ı	-	(*)	LTG RELAY PANEL	RUN THRU		WIRF 60
	SPARE	SPARE 5	SPARE }	SPARE	SAFE I	SPARE	SPARE	SPARE	SPARE	SPARE	RECEPTACLES - CLASSROOMS		SERVES		FEED FROM	0 HZ WAINS: ADDA MLO										
	8 4	82	8	78	76	74	72	70	68	66	64	62	6	58	56	54	52	50	48	4 6	44	C	CKT#			